FND: 2 1/2 B.C.

SEC. 27

PE #7728

C-E 1/16

BOUNDARY LINE ADJUSTMENT

A BOUNDARY LINE ADJUSTMENT ON PROPERTY LOCATED IN THE N.E. 1/4 OF SEC. 27, TWP. 5 NORTH, RNG. 28 EAST OF THE W.M. UMATILLA COUNTY OREGON.

LEGEND

- O SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP STAMPED "PLS LS 48509"
- FOUND 5/8" IRON ROD WITH YELLOW PLASTIC CAP STAMPED "EDWARDS #951"
- FOUND 5/8' IRON ROD SET BY LS #951
- FOUND MONUMENT AS NOTED
- X COMPUTED POINT (NOT SET)

STRUCTURE FOOTPRINTS

_SURVEYOR'S NARRATIVE

THIS SURVEY WAS UNDERTAKEN IN JANUARY OF 2022 AT THE REQUEST OF LESTER B. JONES & JOAN F. JONES. THE PURPOSE OF THE SURVEY IS TO PERFORM A BOUNDARY LINE ADJUSTMENT ON TRACT 1 AND TRACT 3 OF THE PROPERTY AS DESCRIBED ON INSTRUMENT NO. 2021-7310651. THE PROPERTY IS LOCATED IN THE NE 1/4 OF SECTION 27, TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN, UMATILLA COUNTY OREGON.

1" = 150'

THE INTENT OF THIS BOUNDARY LINE ADJUSTMENT IS TO ADJUST THE COMMON NORTH-SOUTH LINE BETWEEN TRACT 1 AND TRACT 3 IN ORDER TO MEET THE 20 FOOT SETBACK DISTANCES TO EXISTING STRUCTURES. THE END RESULT IS THAT TRACT 3 WILL RETAIN THE 4.00 ACRES AND TRACT 1 WILL RETAIN THE 15.48 ACRES WITH THE NEW CONFIGURATION OF THE COMMON NORTH-SOUTH LINE. ONCE THIS BOUNDARY LINE ADJUSTMENT IS RECORDED THE CLIENT INTENDS ON PERFORMING A PARTITION SURVEY OF TRACT 1.

THE EXTERIOR PROPERTY LINES OF BOTH TRACT 1 AND TRACT 3 HAVE BEEN ESTABLISHED FROM THE DEED CALLS AS WELL AS THE FOUND MONUMENTS AS SHOWN. I ELECTED TO SET ALL THE CORNERS FOR THAT PROPERTY AS DESCRIBED ON INSTRUMENT NO. 2021-7310651. THE FOOTPRINTS OF ALL STRUCTURES ON THE PROPERTY HAVE BEEN LOCATED FOR A VISUAL REPRESENTATION TO THE

THE LEGAL DESCRIPTION OF RECORD CONTAINS TYPOGRAPHICAL ERRORS AS SHOWN.

THE BASIS OF BEARING FOR THIS PARTITION SURVEY IS THE FOUND 2 1/2" BRASS CAP MARKING THE NORTHEAST SECTION CORNER TO SECTION 27, TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN AND THE FOUND 2 1/2" BRASS CAP MARKING THE EAST 1/4 CORNER TO SECTION 27, TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN AND IS BASED UPON RECORD OF SURVEY NO. 09-003-A.

NEW LEGAL DESCRIPTION TRACT 1

COMMENCING AT A 2 1/2 INCH BRASS CAP MARKING THE NORTHEAST CORNER FOR SECTION 27. TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN; THENCE S 1°34'03" W. 1319.52 FEET TO A 5/8 INCH IRON ROD ON THE WESTERLY RIGHT OF WAY LINE OF SAGEBRUSH ROAD, AND THE TRUE POINT OF BEGINNING OF THIS DESCRIPTION; THENCE ALONG SAID RIGHT OF WAY LINE S 0°08'03" W, 792.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE LEAVING SAID RIGHT OF WAY LINE N 89°42'53" W, 632.26 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 0°16'35" W. 264.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "EDWARDS #951"; THENCE N 89°42'53" W, 330.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E, 528.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 89°42'53" E, 330.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E, 11.73 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 89°42'53" E, 83.18 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E, 214.76 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509": THENCE N 89°42'53" W, 142.42 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E, 301.51 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 89°42'53" E, 689.54 FEET TO THE POINT OF BEGINNING. CONTAINING 15.478 ACRES.

NEW LEGAL DESCRIPTION TRACT 3


COMMENCING AT A 2 1/2 INCH BRASS CAP MARKING THE NORTHEAST CORNER FOR SECTION 27, TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN; THENCE S 28°52'46" W, 1502.44 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509". AND THE TRUE POINT OF BEGINNING OF THIS DESCRIPTION; THENCE S 0°16'35" W, 301.51 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S E, 142.42 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 0°16'35" W, 214.76 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED " PLS LS 48509"; THENCE N 89°42'53" W. 83.18 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 0°16'35" W. 11.73 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509": THENCE N 89'42'53" W, 330.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E, 528.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE S 89°42'53" E, 270.76 FEET TO THE POINT OF BEGINNING. CONTAINING 4.000 ACRES.

<u>LEGAL DESCRIPTION FROM TRACT 1 TO TRACT 3</u>

COMMENCING AT A 2 1/2 INCH BRASS CAP MARKING THE NORTHEAST CORNER FOR SECTION 27, TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN; THENCE S 19'52'11" W, 1720.21 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509". AND THE TRUE POINT OF BEGINNING OF THIS DESCRIPTION; THENCE S 0°16'35" W, 214.76 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509": THENCE N 89'42'53" W, 83.18 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E. 214.76 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED " PLS LS 48509"; THENCE S 89°42'53" E, 83.17 FEET TO THE POINT OF BEGINNING. CONTAINING 0.410 ACRES.

LEGAL DESCRIPTION FROM TRACT 3 TO TRACT 1

COMMENCING AT A 2 1/2 INCH BRASS CAP MARKING THE NORTHEAST CORNER FOR SECTION 27, TOWNSHIP 5 NORTH, RANGE 28, EAST OF THE WILLAMETTE MERIDIAN; THENCE S 26°51'31" W, 1475.00 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509". AND THE TRUE POINT OF BEGINNING OF THIS DESCRIPTION; THENCE S 0°16'35" W, 301.51 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 89°42'53" W, 59.24 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED "PLS LS 48509"; THENCE N 0°16'35" E. 301.51 FEET TO A 5/8 INCH IRON ROD WITH A YELLOW PLASTIC CAP STAMPED " PLS LS 48509"; THENCE S 89'42'53" E, 59.24 FEET TO THE POINT OF BEGINNING. CONTAINING 0.410 ACRES.



OWNERS ACKNOWLEDGEMENT

KNOW ALL PEOPLE BY THESE PRESENTS THAT WE, LESTER B. JONES & JOAN F. JONES, MANAGING MEMBERS OF AFFORDABLE HOMES OF OREGON, INC. AND OWNERS OF THE LANDS SHOWN ON THIS PLAT AND MORE PARTICULARLY DESCRIBED IN THE ACCOMPANYING LEGAL DESCRIPTION, HAVE CAUSED THE SAME TO SET THE PROPER MONUMENTS. BE SURVEYED AND A BOUNDARY LINE ADJUSTMENT COMPLETED BETWEEN TRACT 1 AND TRACT 3 AS SHOWN ON THIS PLAT.

LESTER B. JONES MANAGING MEMBER OF AFFORDABLE HOMES OF OREGON, INC.

Jan Jones MANAGING MEMBER OF AFFORDABLE HOMES OF OREGON, INC.

THIS DAY 24Th OF FEBRUARY,
APPEARED LESTER B. JONES & JOAN F. JONES, MANAGING MEMBERS OF AFFORDABLE HOMES OF OREGON, INC. TO ME PERSONALLY KNOWN, WHO ACKNOWLEDGED THE FOREGOING PARTITIONING TO BE A FREE AND VOLUNTARY ACT.

KNOW ALL PEOPLE BY THESE PRESENTS THAT ON

COMMISSION NO. 1016081

MY COMMISSION EXPIRES Sept. 25, 2025

SURVEYOR'S CERTIFICATION

I, BRIT L. PRIMM, A PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON HEREBY CERTIFY THAT THIS MAP CORRECTLY REPRESENTS A SURVEY CONDUCTED UNDER MY DIRECT SUPERVISION IN DECEMBER 2021, IN CONFORMANCE WITH THE REQUIREMENTS OF THE SURVEY RECORDING LAW, AS ESTABLISHED BY ORS CHAPTER 92, AND HAVE

AREA TABLE

| FEET 2 | ACRES |
|------------|---|
| 174239.998 | 4.000 |
| 174239.998 | 4.000 |
| 674216.021 | 15.478 |
| 674216.021 | 15.478 |
| 17862.673 | 0.410 |
| 17862.673 | 0.410 |
| | 174239.998 674216.021 674216.021 17862.673 |

REGISTERED **PROFESSIONAL** LAND SURVEYOR

SEC. 27

OREGON JULY 13, 1999 BRIT L. PRIMM 48509 EXPIRATION DATE: 12/31/22

DATE: 17 FEB 22

PRIMM LAND SURVEYING, INC.

P.O. BOX 1322, 1340 N.E. 4TH

HERMISTON, OR 97838

BUI (541) 564-7887

brit@primmlandsurveying.com

FAX (541) 567-8020

keith@primmlandsurveying.com

LEGAL DESCRIPTION OF RECORD

Township 5 North, Range 28, East of the Willamette Meridian

Section 27: The North 1,056.00 feet of the Southeast Quarter of the Northeast Quarter.

Excepting therefrom the West 660.00 feet of the north 528.00 feet.

Also excepting therefrom the South 264.00 feet of the North 1,056.00 feet (Excepting therefrom the West 660 feet thereof).

Also excepting therefrom any portion lying within the County Road

All being East of the Willamette Meridian, Umatilla County, Oregon.

Township 5 North, Range 28, East of the Willamette Meridian

Section 27: The South 264 feet of the North 1,056.00 feet of the Southeast Quarter of the Northeast Quarter.

Excepting therefrom the East 33.00 feet lying in Sagebrush Road.

Section 27: A Non-Exclusive Easement for ingress, egress and utilities over a strip of land 50.00 feet in width, the centerline of which is described as beginning on the West line of the Southeast Quarter of the Northeast Quarter of said Section 27, which lies 1,056.00 feet South of the Northwest corner of said Southeast Quarter and run thence East, parallel with the North line of said Southeast Quarter, a distance of 660.00 feet; thence South, parallel with the West line of said Southeast Quarter, a distance of 264.00 feet, more or less to a point on the South line of said Southeast Quarter and the point of terminus of said 50.00 foot easement.

Section 27: A Non-Exclusive Easement for ingress, egress and utilities over a strip of land 25.00 feet in width, the South line of which is described as beginning on the South line of the Southeast Quarter of the Northeast Quarter of said Section 27, which lines 660.00 feet East of the Southwest corner of said Southeast Quarter, and run thence East, a distance of 130.00 feet more or less to the Northerly line of County Road No. 1264 aka Klaus Road.

All being East of the Willamette Meridian, Umatilla County, Oregon.

Township 5 North, Range 28, East of the Willamette Meridian

Section 27: The East 330.00 feet of the West 660.00 feet of the North 528.00 feet of the Southeast Quarter of the Northeast Quarter.

Section 27: A Non-Exclusive Easement for ingress, egress and utilities over the North 25.00 feet of the Southeast Quarter and over the South 50.00 feet of the North 553.00 feet of said Southeast Quarter.

All being East of the Willamette Meridian, Umatilla County, Oregon.

Township 5 North, Range 28, East of the Willamette Meridian

Section 27: The West 330.00 feet of the North 528.00 the Southeast Quarter of the Northeast Quarter.

Section 27: A Non-Exclusive Easement for ingress, egress and utilities over the North 25.00 feet of the Southeast Quarter and over the South 50.00 feet of the North 553.00 feet of said Southeast Quarter.

All being East of the Willamette Meridian, Umatilla County, Oregon.

TRACT V

Township 5 North, Range 28, East of the Willamette Meridian

Section 27: The South 528.00 feet of the North 1,056.00 of the West 330.00 feet of the Southeast Quarter of the Northeast Quarter.

A Non-Exclusive Easement for ingress, egress and utilities over the South 50.00 feet of the North 553.00 feet of the Southeast Quarter.

Section 27: A Non-Exclusive Easement for ingress, egress and utilities over a strip of land 50.00 feet in width, the centerline of which is described as beginning at the Southwest corner of the South 528.00 feet the North 1.056.00 feet of the West 330.00 feet of the Southeast Quarter of the Northeast Quarter; thence East, parallel with the North line of said Southeast Quarter, a distance of 660.00 feet, thence South, parallel with the West line of said Southeast Quarter, a distance of 264.00 feet, more or less to a point on the South line of said Southeast Quarter.

Section 27: A Non-Exclusive Easement for ingress, egress and utilities over a strip of land 25.00 feet in width, the South line of which is described as beginning at a point on the South line of the Southeast Quarter of the Northeast Quarter of said Section 27, which lies 660.00 feet East of the Southwest corner of said Southeast Quarter, and run thence East, parallel with the North line of said Southeast Quarter, a distance of 130.00 feet more or less to the Northerly line of County Road No. 1624 aka Klaus Road.

All being East of the Willamette Meridian, Umatilla County, Oregon.

CLIENT: LESTER B JONES & JOAN F. JONES

NE 1/4 OF SEC. 27, TWP. 5 N, RNG. 28 E.W.M.

PROJECT:

A BOUNDARY LINE ADJUSTMENT ON PROPERTY DATE: 10 JAN 22 LOCATED IN THE N.E. 1/4 OF SEC. 27, TWP. FB/PG: 5 NORTH, RNG. 28 EAST OF THE W.M. UMATILLA COUNTY OREGON.

JOB #: 2201001 SHEET: 1 OF 1 DRAWN: BLP APPROVED: BLP

DEEDS INST. # 2021-7310651

SURVEYS R.O.S. 09-003-A

NOTES (D) DEED

(C) CALCULATED () R.O.S. 09-003-A